

Miami Beach – Lessons Learned from Free Sand

2017 FSBPA Annual Conference

Tim Blankenship, P.E.
Moffatt & Nichol
Coconut Grove, Florida

Elizabeth Wheaton, AICP, LEED AP+C
Office of the Mayor and City Commission
City of Miami Beach, Florida



moffatt & nichol

Creative People, Practical Solutions.®



Presentation Agenda



Project - Miami Beach

- Miami Dade County Beach Management
 - Project of Opportunity – Oceanfront Development
 - Beach Nourishment, Consent Order and Remediation
 - City Ordinance Development
 - Conclusions and Lessons Learned
- 

Miami-Dade County Beach Management

- Federal Government – US Army Corps of Engineers
 - State Government - Owner & Regulator
 - Miami Dade County – Local Sponsor
- ~ 23 million cy over next 50yrs
 - ~ 3.6 million cy needed for the remaining period of federal participation:
 - 10 yrs: Baker's Haulover to Government Cut
 - 23 yrs: Sunny Isles Segment



THE BACKGROUND

Beach renourishment has been an ongoing practice in southeast Florida since the late 1970s, providing essential economic, environmental and recreational benefit to coastal communities. Renourished beaches and dunes serve as a vital buffer between coastal infrastructure and the destructive forces of ocean waves and surge during storm events.



The southeast Florida region encompasses five counties (St. Lucie, Martin, Palm Beach, Broward, and Miami-Dade) and approximately 200 miles of Florida shoreline (Figure 1). Throughout the region, twenty-four federal and non-federal beach nourishment projects provide storm damage reduction to infrastructure as well as incidental recreational opportunities for local, national and international visitors.

These constructed beaches mimic the protective and recreational functions of natural beaches, and the resulting benefits of beach nourishment projects are well documented. The 2008 Shore Protection Assessment completed an in-depth evaluation of benefits provided by the Martin County Shore Protection Project during the 2004 hurricane season. The study calculated more than \$11 million in damages were prevented by the project. This equals approximately 20 percent of the 50 year total project cost, realized in one storm season. As an example of recreational benefits, Miami Beach had little beach tourism before construction of the Dade County Beach Erosion Control and Hurricane Protection Project in 1975. Since construction of the project, it is estimated that tourists contribute \$11 billion annually to the Miami Beach economy, almost half of which comes from international tourists.

Sand dredged from offshore borrow sources in state and federal waters is typically used to renourish the beaches. The current practice is for projects to access borrow sources located in close proximity to the project, since they are often the most economical sand sources. Counties are often cost-sharing partners in the projects, along with the state of Florida and the federal government (in the case of federal projects). Many of these projects were initially constructed in the 1970's and 1980's, and are periodically renourished with sand over a typical project life of 50 years.

Renourishment needs of ongoing projects, initiation of new projects, existing environmental resources, and increasing environmental constraints have continued to reduce the available sand supply located offshore, particularly in Broward and Miami-Dade. In these southernmost counties, narrowing of the continental shelf limits investigation and access to sand sources. Currently, sand sources offshore of these two counties fall short of the counties' renourishment needs throughout their projects' remaining periods of federal participation.

Miami-Dade County, in particular, is running out of dependable, economical, and environmentally practicable offshore sand sources. In 1986, a congressional directive authorized the acquisition of non-domestic sand if such material is not available from domestic sources for environmental or economic reasons. Since that time, the U.S. Army Corps of Engineers (Corps) has been investigating the use of non-domestic sand for use on federal projects in southeast Florida, particularly in Miami-Dade County.

Investigations for Miami-Dade County indicated that some sources, particularly Bahamian aragonite, which has been used on non-federal projects in southeast Florida, looked promising. However, in 1999 the fiscal year 1999 Energy and Water Appropriations Bill directed that no funds provided for the Dade County, Florida shore protection project be used for acquisition of foreign source materials unless the Secretary of the Army provides written certification that domestic sources are not available.

PROJECT SCHEDULE:

The Corps is in the process of completing a Limited Re-evaluation Report (LRR) and NEPA documentation to utilize sand as discussed above. It is anticipated that this report will be approved around March 2016. From that point, the Corps would start permit applications and detailed designs with construction contracts awarded in 2016 (subject to appropriations).



Sunny Isles Truck Haul Nourishment Costs


- 2017 Project – Miami-Dade County
- Maintenance Project – Truck Haul
- Corps Estimate \$71/cy – 100,000cy Project
- 8 bidders
- Beach fill unit costs ranged \$60 -\$105 per cy

Chateau Ocean Residences – Surfside, FL



<http://fendichateauridences.com>

Chateau Development Site Plan



CHATEAU OCEAN RESIDENCES
 1000 COLLIER HARBOR DRIVE, FL 33069
 COUNTY OF DADE, FLORIDA
 CHATEAU GROUP
 1800 N.W. 22ND AVE. SUITE 200 MIAMI, FL 33135

ARCHITECT OF RECORD
ARQUITECTONICA
 2600 N.W. 10TH AVE.
 MIAMI, FL 33135
 305.571.1000
 www.arquitectonica.com

STRUCTURAL ENGINEER
 SITE PLAN APPROVAL REV.

M.E.P. ENGINEER

LANDSCAPE ARCHITECT
ARQUITECTONICA ASD
 2600 N.W. 10TH AVE.
 MIAMI, FL 33135
 305.571.1000
 www.arquitectonica.com

CIVIL ENGINEER
 1800 N.W. 22ND STREET SUITE 200
 MIAMI, FL 33135
 305.571.1000

CONSULTANT
FORTINER LEVY SKILES, INC.
 10000 SW 15TH AVE., SUITE 100
 MIAMI, FL 33187
 305.571.7700

CONSULTANT

SCALE / SIGNATURE / DATE

SITE PLAN APPROVAL
 OFFICE REGISTRATION NUMBER
 Date: 10/15/2015 Revision: 1


Issue	Date	Issue State / For
01.12.15	01.12.15	SITE PLAN APPROVAL
02.03.15	02.03.15	SITE PLAN APPROVAL COMMENT
02.11.15	02.11.15	SITE PLAN APPROVAL COMMENT
03.03.15	03.03.15	SITE PLAN APPROVAL REVISION
03.10.15	03.10.15	SITE PLAN APPROVAL COMMENT
03.18.15	03.18.15	SITE PLAN APPROVAL REVISION

ARIQ Project No.: 0090
 Drawn by: L.A.
 Approved by: S.H.

SHEET INDEX
SITE PLAN

L-100

- FDEP CCCL Permit
- 20,855 cy excavation



Coastal Construction Control Line (CCCL)

NOTE
 FOR HARDSCAPE PLAN & SCHEDULE
 SEE L-110
 FOR TREE PLANTING PLAN &
 SCHEDULE SEE L-120
 FOR SHRUBS & GROUND COVER
 PLAN & SCHEDULE SEE L-130

55 Street Erosional Hotspot – Miami Beach




55 Street Erosional Hotspot



Beach Nourishment Plan Areas


Southern
erosional
hotspot



CHAPEL BEACH FILL REMEDICATION PROJECT MIAMI BEACH, FL	
D	
C	
B	
A	
Sheet Reference No. FIG-001	

Fill section R-48

PERMIT # 233 882 005



LEGEND:

 PROPOSED FILL AREA

P:_Drafters\IPong\2009_0209_BeachRestoration_Survey_2008_Juan\2008_Miami_Beach_SDI_R35_TO_R61_Read\meldwg\2008_Design_R41_R48+700_design-temp.dwg
PDF File: R-46.pdf

JUAN A. CURIEL
State of Florida
Professional Engineer
License No. 63890

MIAMI-DADE COUNTY DERM
WATER MANAGEMENT
DIVISION

701 NW 1st Court, 5th Floor
MIAMI, FLORIDA 33136

MIAMI BEACH AREA
TRANSECTS R-46

JOB: R44+500 to R48+700 DATE: 07-28-09
BY: J.C. / M.P. SHEET: 3/7

Observations after Fill Placement



Stal *


R 48.0W (North End)	Surf elev. Bottom of fill elev. pieces of debris/ cu ft			R 48.0M	Surf elev. Bottom of fill elev. pieces of debris/ cu ft
Profile				Profile	
R 48.1W (North End)	Surf elev. Bottom of fill elev. pieces of debris/ cu ft	NAVD	type debris	R 48.1M	Surf elev. Bottom of fill elev. pieces of debris/ cu ft
Profile				Profile	
R 48.2W (North End)	Surf elev. Bottom of fill elev. pieces of debris/ cu ft	NAVD	type debris	R 48.2M	Surf elev. Bottom of fill elev. pieces of debris/ cu ft
Profile				Profile	
R 48.3W (North End)	Surf elev. Bottom of fill elev. pieces of debris/ cu ft	NAVD	type debris	R 48.3M	Surf elev. Bottom of fill elev. pieces of debris/ cu ft
Profile				Profile	
R 48.4W (North End)	Surf elev. Bottom of fill elev. pieces of debris/ cu ft	NAVD	type debris	R 48.4M	Surf elev. Bottom of fill elev. pieces of debris/ cu ft
Profile				Profile	
R 48.5W (North End)	Surf elev. Bottom of fill elev. pieces of debris/ cu ft	NAVD	type debris	R 48.5M	Surf elev. Bottom of fill elev. pieces of debris/ cu ft
Profile				Profile	
R 48.6W (North End)	Surf elev. Bottom of fill elev. pieces of debris/ cu ft	NAVD	type debris	R 48.6M	Surf elev. Bottom of fill elev. pieces of debris/ cu ft
Profile				Profile	
R 48.7W (North End)	Surf elev. Bottom of fill elev. pieces of debris/ cu ft	NAVD	type debris	R 48.7M	Surf elev. Bottom of fill elev. pieces of debris/ cu ft
Profile				Profile	
R 48.8W (North End)	Surf elev. Bottom of fill elev. pieces of debris/ cu ft	NAVD	type debris	R 48.8M	Surf elev. Bottom of fill elev. pieces of debris/ cu ft
Profile				Profile	
R 48.9W (North End)	Surf elev. Bottom of fill elev. pieces of debris/ cu ft	NAVD	type debris	R 48.9M	Surf elev. Bottom of fill elev. pieces of debris/ cu ft
Profile				Profile	



Beach Nourishment Plan Areas

Northern area with most concentrated amount of debris

Southern erosional hotspot



CHATEAU BEACH FILL REMEDATION PROJECT MIAMI BEACH, FL	
MAJOR DEMARICATION PROJECT LIMITS	
DATE	BY
2015-08-27	TR
DATE	BY
2015-08-27	TR
DATE	BY
2015-08-27	TR
DATE	BY
2015-08-27	TR
DATE	BY
2015-08-27	TR
DATE	BY
2015-08-27	TR
DATE	BY
2015-08-27	TR
DATE	BY
2015-08-27	TR

SCALE: 1"=80'

FOR INFORMATION ONLY

Sheet Reference No.
FIG-001

Nourishment Timeline

- Public Outreach – Fall 2014
- CCCL Permit Modification Issued - February 2015
- Fill Placed March 2015
- FDEP Issued Compliance Letter – May 2015
- Consent Order Fill Remediation - March 2016
- Remediation Operations March-April, 2016
- Remediation Close Out - July, 2016


Debris and Thickness Observations

March 2016 Test Pit Excavation Data											
55th Street Beach Fill (DEP Permit No. DA-647 M1)											
R-48.2W to R4.9E											
Profile		NAVD	Depth of Fill in ft	Profile		NAVD	Depth of Fill in ft	Profile		NAVD	Depth of Fill in ft
R48.2 W	Top Fill	7.5	1.1	R48.2 M	Top Fill	7.2	0.6	R48.2 E	Top Fill	7.4	0.3
	Btm. Fill	6.4			Btm. Fill	6.6			Btm. Fill	7.1	
	Pieces of debris		2 (concrete and old wood)		Pieces of debris		1 (old wood)		Pieces of debris		1 (glass)
R48.3 W	Top Fill	7.7	0.7	R48.3 M	Top Fill	7.6	1.4	R48.3 E	Top Fill	7.1	0.2
	Btm. Fill	7			Btm. Fill	6.2			Btm. Fill	6.9	
	Pieces of debris		2 (tile, old wood)		Pieces of debris		3 (old wood and metal)		Pieces of debris		1 (tile piece)
R48.4 W	Top Fill	7.6	1.2	R48.4 M	Top Fill	7.2	0.6	R48.4 E	Top Fill	6.7	0.7
	Btm. Fill	6.4			Btm. Fill	6.6			Btm. Fill	6	
	Pieces of debris		12 (glass, old wood, concrete, rubber sealant, rock)		Pieces of debris		4 (glass, concrete, rock)		Pieces of debris		4 (glass, concrete, rock)
R48.5 W	Top Fill	7.4	0.4	R48.5 M	Top Fill	7.5	0.7	R48.5 E	Top Fill	7.1	0.6
	Btm. Fill	7			Btm. Fill	6.8			Btm. Fill	6.5	
	Pieces of debris		10 (glass, old wood, metal, concrete, rock)		Pieces of debris		7 (glass, nails, old wood, concrete, plastic)		Pieces of debris		4 (glass, old wood, plastic)
R48.6 W	Top Fill	7.2	0.9	R48.6 M	Top Fill	7.5	0.6	R48.6 E	Top Fill	7.6	0.1
	Btm. Fill	6.3	(no photo)		Btm. Fill	6.9	(no photo)		Btm. Fill	7.5	
	Pieces of debris		4 (descript. not logged)		Pieces of debris		3 (descript. not logged)		Pieces of debris		2 (glass, nail, concrete)
R48.7 W	Top Fill	6.9	0.6	R48.7 M	Top Fill	7.3	0.6	R48.7 E	Top Fill	7.3	0.1
	Btm. Fill	6.3			Btm. Fill	6.7			Btm. Fill	7.2	
	Pieces of debris		11 (tile, glass, nails, concrete, old wood, rock)		Pieces of debris		4 (glass, concrete, plastic, old wood)		Pieces of debris		4 (tile, concrete, old wood, rock)
R48.8 W	Top Fill	7.2	1.1	R48.8 M	Top Fill	7.5	0.5	R48.8 E	Top Fill	NAVD	Depth of Fill in ft
	Btm. Fill	6.1			Btm. Fill	7			Btm. Fill		very thin fill layer
	Pieces of debris		12 (glass, nail, old wood, tile, concrete, rock)		Pieces of debris		5 (glass, concrete, rock, plastic)		Pieces of debris		0
R48.9 W	Top Fill	7.6	0.7	R48.9 M	Top Fill	7.5	0.3	R48.9 E	Top Fill	7.2	1.1
	Btm. Fill	6.9			Btm. Fill	7.2			Btm. Fill	6.1	
	Pieces of debris		10 (concrete, rock, old wood)		Pieces of debris		5 (concrete, rock)		Pieces of debris		5 (glass, concrete, rock, plastic)




04.20.2016 11:24

Remediation Operations



Mined Sand Issues



Miami Beach Sand Ordinance – June 2016

1. Municipalities have authority to promulgate setbacks, building codes, and land development regulations stricter than the state
2. Sets forth physical characteristics and chemical composition
3. Require DERM Soil Classification Letter
4. Requires Developer to pay for the cost of beach compatibility testing

Conclusions and Lessons Learned

- Project of Opportunity – still recommended
- Costs of Beach Nourishment – continue to increase
- Proper Project oversight and QA/QC on sand source
- Joint Coastal Permits in Place for Maintenance
- Municipal Perspective
- City Ordinance Development – Beach Sand

Hurricane Irma Beach Impacts



Pre-Storm



Post-Storm



THANK YOU!



moffatt & nichol

