

Kennedy Space Center Dune Restoration

Michael Jenkins, PhD, PE; Senior Principal; ATM – A Geosyntec Company

Kim Rivera, PE; Department Manager; Jones Edmunds

Pete Seidle, PE; Moffat-Nichol

2022 National Conference on Beach Preservation Technology


St. Augustine Beach, FL

February 3, 2022



JonesEdmunds


The Project Site




Google Earth

Data SIO, NOAA, U.S. Navy, NGA, GEBCO

The Project Site



Sandy, Mathew and Dorian




2012

2016

2019

Post Sandy Dune Restoration




Dune Breach – Hurricane Mathew



Site Constraints


- Receding Headland - Shoreline Retreat
- Upland Infrastructure
- Coastal Wetlands
- Critical Habitat
- Operational Space Port (NASA - KSC)

SBEACH Modeling



- ❑ SBEACH analysis showing the effects of 25 year storm on V-81.
- ❑ 7.8 CY/lf loss.
- ❑ SBEACH inputs based on FDEP published settings for 15 and 25 Year storm simulation for Volusia County, FL.

Typical Dune Cross Section



Sand Sources



- Sand source specifications - Grain Size, Munsell Color and Chroma ([Florida Rule 62B-41.007](#))
- Standard Practice for Dune Placement
- Grain Size, General Color, Silt Fraction, Gravel Fraction and Debris
- QA and QC Procedures
- Monitoring and Testing

Sand Sources



4/20/2017

LEGEND:

-  RECOMMENDED SOIL TESTING LOCATIONS
-  NASA ENVIRONMENTAL ADDITIONAL LOCATIONS



Sand Sources

- On-Center:
 - ❑ KSC Beach line Samples (baseline) - passed
 - ❑ All KSC Locations (3) – failed (samples finer characteristics, darker color)
 - ❑ CCAFS samples (Titan and DMMA) – passed

- Off-center:
 - ❑ (Cemex Davenport and Central Sand Tico) – passed
 - ❑ other sources (6) – failed specifications or inadequate quantity

Project Construction



Project Construction



Project Construction



Project Construction



Completed Project



Construction Summary

Phase 1 and 1A (Completed Spring 2019)

- **Phase 1:** 340,000cy over 14,700ft (23.1 cy/lft)
- **Phase 1A:** additional 110,000cy over 5,000 ft (22 cy/lft) (back side of dune)

Phase 2 and Dorian-Post

- **Phase 2:** 70,000 cy over 4,500 ft (15.6 cy/lft)
- **Dorian-Post:** 35,000cy over 2,000 ft (back side of dune) (17.5 cy/lft)

Total: 555,000 CY over 3.6 Miles (avg. density 29.2 CY/lft)

Lessons Learned

- Complexities of dune construction on a receding shoreline
- Vulnerability of transition zones and project limits
- Bad things come in 3's (Sandy, Mathew and Dorian)



Upcoming Launches

February – Falcon 9 (Starlink)

March 1 – Atlas 5 (Geos T)

Early 2022 – Falcon Heavy (US Space Force)

March 20 – Artemis-SLS (Heavy lift)

