

# INDIAN RIVER COUNTY SECTOR 3 BEACH AND DUNE RESTORATION PROJECT

James Austin, Coastal Engineer, APTIM

Nicole S. Sharp, P.E., Coastal Market Lead, APTIM

Eric Charest, Natural Resources Manager, Indian River County Public Works






#### **ACKNOWLEDGMENTS**

- ► Indian River County:
  - > Eric Charest
  - > Quintin Bergman
- ► APTIM:
  - > Erica Carr-Betts
  - > Doris Otero
  - > Katy Brown
- ► CPE:
  - > Stacy Buck
- ► EAI:
  - > Grace Botson
  - > Joey Pessolano









# **PROJECT LOCATION**








#### **SECTOR 3 HISTORY**

- ► Indian River County's coastline is divided into 8 sectors
- ► Sector 3 is approximately 7.1 miles
- ► Nourishments done by sector










#### **SECTOR 3 HISTORY**

- Suffers from erosion and storm events
- ► Large scale nourishment is relatively new solution for Sector 3
- ► Small scale post-storm dune maintenance in 2004 and 2005
- First sector-wide beach nourishment occurred from 2010 to 2012
- ▶ Dune restoration in 2014/15 (Post-Sandy)
- ► Small scale post-storm maintenance in 2017 and 2018 (Post-Matthew and Irma)


















# **PROGRAM HISTORY**

November 2008












#### **SECTOR 3 ENGINEERING GOALS**

- Mitigate for losses to initial design
- Maximize storm protection
- Avoid hardbottom impacts
- ► Restore/maintain recreational beach
- Habitat for nesting sea turtles and shorebirds
- Develop a constructable fill template








#### **HURRICANE DORIAN**

- Devastating Category 5 hurricane
  - > Peak intensity 185 mph
- ► Made 2 landfalls in the Bahamas
- ► Eye passed ~100 miles offshore of **Indian River County**










#### **HURRICANE DORIAN IMPACTS**



- ► Large wind field and slow progression resulted in erosion
- ► 72,000 CY of loss
- ► Hurricane force winds extended 60 miles from center
- Produced wave heights of 15 ft offshore of the County's coastline








#### 2021 PROJECT ELEMENTS

- ► New project design for increased protection
- Restore dune with narrow berm
- Project was designed to nourish Sector 3 in two phases
  - > Phase 1: January 2021 to December 2021
  - > Phase 2: November 2021 to March 2022
- Designed to address background erosion and storm damage
- Truck Haul from Stewart Materials in Ft. Pierce
- Permit limits construction to occur between November 1 and May 1.
- ▶ 6.6 miles of shoreline









#### **BIDDING APPROACH**

- ► Phase 1 went out to bid October 2020
- ► Phase 2 went out to bid August 2021



- ► Phase 1 lowest bid = \$11,987,010
- ► Phase 2 lowest bid = \$14,174,738







#### **FUNDING**

► FEMA: \$9.75 million

► FDEP: \$7.32 million












#### PRE-CONSTRUCTION CHALLENGES

- Easements
- ► A County requirement for placement of sand
- Allow for use of beach by public and for construction
- ► GIS map with current easement status
- www.ircgov.com/easements









## PRE-CONSTRUCTION CHALLENGES

- Nearshore Hardbottom
  - > Avg. distance to shoreline = 257 ft
  - > Avg. depth = -12 ft NAVD
- Designed to avoid hardbottom
- ► Permits restricted covering of hardbottom
  - > No mitigation required














#### **CONSTRUCTION CHALLENGES**

- Sea turtles
- ▶ 500 ft buffer from sea turtle nest
- Nest dictated construction method









## **CONSTRUCTION AND THE PUBLIC**









#### **DUNES**

- Sector-wide dune constructed and planted
- ► Required coordination with property owners for dune walkovers
- Seawalls prevented dunes in some areas







#### **VEGETATION**

- ▶ Dune crest was planted approximately 18" O.C.
- ► 713,359 total plants
  - > 587,477 sea oats
  - > 50,353 panic grass
  - > 75,529 railroad vine
  - > 75,529 dune sunflower
  - > 75,529 beach elder









#### **CONSTRUCTION SUMMARY AND STATS**



- Constructed between January 1, 2021 and March 2, 2022
- ► Contractor = Guettler Brothers Construction, LLC
- ► 552,400 CY placed
- ▶ 5 beach parks used as construction access.



#### 2021 Pre-Construction

#### 2022 Post-Construction





Wabasso Beach Park











Golden Sands Beach Park





#### **HURRICANE IAN**

- Devastating Category 4 hurricane
  - > Peak intensity 155 mph
- ► Made Landfall in Lee County
- ► Impacted IRC as tropical storm









#### **HURRICANE IAN IMPACTS**

- ► Large storm surge and wave action
- ► Wind gusts up to 65 mph
- ► Caused escarpments 2 to 6 feet
- Substantial dune impacts











#### **HURRICANE NICOLE**

- ► Category 1 hurricane
  - > Peak intensity 75 mph
- ► Made 2 landfalls in Florida
  - > South of Vero Beach
  - > Northwest of Cedar Key
- ► Impacted with Indian River County directly










#### **HURRICANE NICOLE IMPACTS**



- ► High storm surge and wave action
  - > Resulted in some loss of infrastructure
- ► Wind gusts up to 58 mph
- ► Caused escarpments 4 to 6 feet
- Substantial dune impacts







#### **HURRICANE NICOLE IMPACTS**

Pre-storm Post-storm





Wabasso Beach Park







## **HURRICANE NICOLE IMPACTS**

Pre-storm



Post-storm



**Turtle Trail Beach Access** 








# PRELIMINARY RESULTS

- ► 275,900 CY of loss above MHW
- ► 153,400 CY of loss above DOC
- Upland infrastructure was minimally impacted due to dune in place







#### **NEXT STEPS**

- ► County implemented a post-storm survey
- ► Losses are being assessed
- ► County is coordinating with FEMA
- ► Emergency projects at County parks







#### **CLOSING REMARKS**

- ► Storm impacts and background erosion contribute to critically eroded designation
- Design limited by factors such as hardbottom
- ► Balance between protecting infrastructure with environment
- ► Sector 3 benefits from frequent renourishments
- Recent hurricanes contributed to dune loss







# **QUESTIONS?**

#### **JAMES AUSTIN**

james.austin@aptim.com 904.252.7401

#### **NICOLE SHARP, P.E.**

nicole.sharp@aptim.com 561.361.3150

#### **ERIC CHAREST**

echarest@ircgov.com 772.226.1569







**Expect the Extraordinary.**