



Johnson Tract Lagoon Tidal Connectivity Study

Todd DeMunda, PE (Stantec) Matt Starr, PG (Stantec) Taylor Kroll (FWC)



Overview

Stantec was tasked by Florida Fish & Wildlife Conservation Commission (FWC) to conduct a tidal connectivity study of their Johnson Tract property in order to increase water exchange and facilitate habitat recovery and enhancement.

Location:

tantec

Western Florida Keys (1) Upper Sugarloaf Sound (2) Johnson Tract Lagoon (existing culvert connection in red)



Overview

Tasks

- Existing conditions assessment
- Tide data collection
- Hydrodynamic model
 development
- Conceptual design alternatives
- Model results and recommendations



Existing Data

Bathymetry/Topography

- 2018-2019 NOAA LIDAR
- 3 ft spatial resolution





Existing Data

Wind

- NOAA Station KYWF1
- Measured data 2005-present
- 8.5 mph average speed
- 79 mph maximum speed



Wind Rose, Annual, 2005-2020



Existing Data

Tides and Water Levels

- NOAA subordinate stations
 - Datums only
 - Based on offsets from Key West
- ADCIRC Tidal Database

Stantec

- Harmonic constituents
 only
- Based on advanced
 numerical modeling



Data Collection

Water Levels

- 2 gauges inside Lagoon
- 1 gauge just outside of Lagoon in Sound
- 1 gauge north of US-1
- 1-month collection period (February 2022)







Data Collection

Water Levels

Stantec

- Compared tidal harmonics
 from field to ADCIRC DB
- Good agreement at gauge N of US-1
- Less accurate S of US-1
- ADCIRC DB is not highly detailed in this area
- No comparison possible in Lagoon



| Source | Constituent | | M2 | S 2 | N2 | K1 | 01 |
|-------------|-------------|-------|--------|------------|--------|--------|-------|
| Field/UTide | amplitude | (ft) | 0.30 | 0.10 | 0.03 | 0.15 | 0.18 |
| | phase | (deg) | 229.35 | 276.73 | 200.48 | 115.38 | 94.58 |
| ADCIRC | amplitude | (ft) | 0.24 | 0.08 | 0.03 | 0.19 | 0.19 |
| | phase | (deg) | 223.26 | 247.74 | 220.97 | 98.30 | 97.10 |

Model Development

Boundary Conditions

- Field data collection period
- Measured water level at N boundary
- Harmonic constituents from ADCIRC DB at all other boundaries
- Spatially uniform, timevarying wind from KYWF1





Model Development Bathymetry and Grid

- 26 ft (8 m) spatial resolution
- Parameterized culverts





Model Results

Water Levels

tantec

- Sound gauge (top) replicated reasonably well
- Lagoon gauge (bottom)
 encountered difficulties
 - Parameterization of culverts
 - Very small (0.5 ft) range
 - Potential unknown groundwater and seepage effects



Conceptual Alternatives

Culvert Additions

- 4 alternative locations
- 6-18 24" culverts at/close to bottom grade
- Massless, conservative tracer initialized in Lagoon (blue) at model start



| Parameter | Alternative A Access Road | Alternative B Narrow Loop Road | Alternative C NW Mangroves | Alternative D Loop/Access Tee |
|--|------------------------------|-----------------------------------|-------------------------------|----------------------------------|
| Culvert section width (ft) | 60 | 80 | 120 | 50 |
| Culvert length (ft) | 90 | 150 | 150 | 90 |
| Number of 24" culverts | 6/12/18 | 6/12/18 | 6/12/18 | 6/12 |
| Invert elevation, inside (ft NAVD88) | -1.5 | -1.5 | -0.5 | -0.5 |
| Roadway elevation (ft NAVD88) | 2.0 | 2.7 | 2.5 | 2.5 |
| Invert elevation, outside (ft NAVD88) | -1.5 | -1.5 | -0.5 | -0.5 |

Model Results Tracer Residence Time

- Only Alt B has appreciable effect
- Not enough available flow at other locations





Model Results Alternative B

 More culverts results in more exchange (with diminishing returns)





Model Results

Alternative B

- Time to 50% of initial concentration
- Concentration
 after 1 month
- Both metrics exhibit similar reduction numbers
- 6 culverts: 48% increase in exchange
- 12 culverts: 69%
- 18 culverts: 78%

tantec



Model Results

Inundation Extents

- Slight increase in E/S mudflat areas
- Little to no difference on vegetated shorelines





Model Results

Inundation Extents

- Slight increase in E/S mudflat areas
- Little to no difference on vegetated shorelines





Next Steps

Full Design

- Awaiting FWC budget
- Anticipating FY2024

Permitting and Construction

• Following design phase

Post-Construction Monitoring

tantec

• How well did the model do in predicting exchange increase?





⋇

todd.demunda@stantec.com

