

The Juno Beach Shore Protection Project and Oyster Reef Restoration in the Loxahatchee River

(or... Making Lemonade out of Lemon-Sized Rocks)

Leanne Welch


Palm Beach County Dept of Env. Resources Mgmt

Bud Howard

Loxahatchee River District

Kathy Fitzpatrick

Martin County Engineering Department





(We are here)

(Juno Beach)







11.04.2008

Permit History

- **Planned Construction:** November 2008
- **Pre-application meeting:** April 2007
- **Application Date:** May 2007
- **Public Notice Published:** October 2007
- **RAIs received:** 1 Federal, 5 State
- **Receipt of USFWS BO:** September 2008
- **Receipt of NMFS BO:** January 2009
- **USACE Permit Received:** March 2009



A new borrow area, located in 70 fsw, offshore of Singer Island, FL was coarser and more similar to the native beach than the previous sand source. Seismic and sub bottom profiling combined with 42 vibracores showed a consistent borrow area, with enough beach quality material for the next two nourishment projects... or so it was thought






Figure 4. Spatial array of 2005 cores from the Singer Island survey area. The occurrence of scattered rock rubble in cores is shown in the yellow pattern.



DRILLING LOG		DIVISION		INSTALLATION		SHEET 1 OF 1 SHEETS	
1. PROJECT Singer Island 2005				9. SIZE AND TYPE OF BIT 4.0 in.			
2. BORING DESIGNATION SI-05-62		LOCATION COORDINATES X = 973,715 Y = 907,180		10. COORDINATE SYSTEM/DATUM Florida State Plane East		HORIZONTAL NAD 1983	
3. DRILLING AGENCY S.E.A., Inc.		CONTRACTOR FILE NO.		11. MANUFACTURER'S DESIGNATION OF DRILL 4-inch pneumatic		VERTICAL NGVD 29	
4. NAME OF DRILLER Alpine Ocean Seismic Survey				12. TOTAL SAMPLES 5		DISTURBED <input type="checkbox"/> AUTO HAMMER <input type="checkbox"/> MANUAL HAMMER UNDISTURBED (UD)	
5. DIRECTION OF BORING <input checked="" type="checkbox"/> VERTICAL <input type="checkbox"/> INCLINED		DEC. FROM VERTICAL		13. TOTAL NUMBER CORE BOXES 2		14. ELEVATION GROUND WATER	
6. THICKNESS OF OVERBURDEN 0.0 Ft.		7. DEPTH DRILLED INTO ROCK 0.0 Ft.		15. DATE BORING STARTED 06-04-05 COMPLETED 06-04-05		16. ELEVATION TOP OF BORING -52.4 Ft.	
8. TOTAL DEPTH OF BORING 19.9 Ft.		17. TOTAL RECOVERY FOR BORING 20.2 Ft.		18. SIGNATURE AND TITLE OF INSPECTOR Gary Zanillo, PG SEA, Inc			

ELEV. (ft)	DEPTH (ft)	LEGEND	CLASSIFICATION OF MATERIALS Depths and elevations based on measured values	REMARKS
-52.4	0.0			
			Gray fine sand, light gray (10YR-7/1), (SP).	1.0 Sample #1.0, Depth = 1.0'
			Gray fine sand, scattered whole shells and shell fragments in fine to coarse gravel range, gray (10YR-6/1), (SP).	5.0
			Tan medium to fine sand, 1.5" white coral rock fragment at 7.1', coral rock fragments in medium to coarse gravel range, tan to white shell fragments and whole shells in fine to coarse gravel range, (10YR-5.5/3), (SP).	7.4
			Tan fine sand, scattered white to tan shell fragments and whole shells in fine gravel range, (10YR-6.5/3), (SP).	10.8
			Tannish gray fine sand, trace of white shell fragments in fine gravel range, (10YR-6.5/2), (SP).	15.0
				Com
				20.2



From the Geotechnical Report: "Some cores contained intervals of very coarse shell material ranging in size from fine to coarse gravel. Occasionally whole shells and rock fragments in the coarse gravel to cobble size range were recovered. The coarse shell material and rock rubble deposits are considered to be lag deposits resulting from storms rather than part of a continuous deposit of either shell or rock."



FLORIDA DEPT. OF ROADS & TRANSPORTATION
 SAJ FI JUN 02

Let's Build a Beach!

- Dredge R.N. Weeks on site 12/20/2009
- Beach complete 3/26/2010
- 1,093,857 cu yds pumped onshore
- Mean GS 0.41 mm (range 0.30 – 0.57mm)
- Relocated 8 leatherback nests out of construction area
- Approximately ½ the costs funded by FEMA (Hurr. Frances, TS Fay)
- Remainder split 50/50 w/DEP









02/18/2010





With the very first load, it became apparent that the geotechnical reports did not tell the whole story of what was in the borrow area...







1) Dredge from a different part of the borrow area



Result: Finer sand... and rocks

2) Add'l Screening on the Dredge...





Result: Clogged screens and angry contractors



3) Add screens at end of discharge pipe





**Result: Clogged boxes, backed up discharge pipes, and...
angry contractors**



4) Post construction screening of fill...





Result: Clean sand on beach; rocks removed, safe beach for tourists, residents, and sea turtles!



Screening of Beach...

- **Construction Dates: 3/15 – 4/30/2010**
- **Dry berm screened to 5' depth**
- **Volume of fill screened = 211,000 yd³**
- **Total rock screened from beach = 6457 tons**
- **Cost ~ \$1,000,000**







But... What do we do with these rocks?







NOAA, Martin County & Loxahatchee River District's Oyster Restoration Project



Bud Howard

Director of Water Resources
Loxahatchee River District



Loxahatchee River District

Protection & Preservation of the Loxahatchee River

- Jupiter, FL
- Special District
- Wastewater Treatment
- Water Recycling – I.Q. Smart Water
- Environmental Education
- WildPine Ecological Laboratory



Oysters




Besides being good to eat...


- Amazing water filtering capacity
- Habitat value – home to > 300 species (e.g., fish, crabs, shrimp, worms, etc.)
- Globally 85% oyster reefs lost



Loxahatchee River Oysters

- Historically oysters widespread through estuary
- Habitat and water quality changes since 1950's





Loxahatchee River 1964

Today




The Need for Oyster Restoration

- Water quality data suggests substrate limited
- What if we provide substrate?
- Have a good seed source of naturally occurring oysters
- Pilot Projects very successful



Going Big - Oyster Restoration

- Stimulus funding through NOAA
- Martin County (Kathy Fitzpatrick) Dream Team
- Permits in <30 days!
- \$4m Grant from NOAA
 - 22 acres in St. Lucie River
 - 3.5 acres in Loxahatchee River



Cultch

Cultch - fossilized shell



Trash ...



... to Treasure!



Collaboration = Savings = More Habitat

- Original Material Cost
 - 3,000 cy @ \$34.50cy = \$103,500




- Palm Beach County's Juno Beach Material
 - Free!
 - Minimal haul
 - 6 additional days of Construction




Construction







Final Construction Areas



Project Benefits

5.84 acres of new oyster reef (3.5 acres planned)

100,000,000 gallons water filtered per day!

Habitat for countless organisms



Valuable Lesson

- Communicate with Colleagues!
 - Collaboration leads to Success-
 - NOAA Funding
 - Material Cost Savings
 - Never know when the next win-win opportunity will arise



Thank you





Leanne Welch: LWelch@pbcgov.org
Kathy Fitzpatrick: kfitzpat@martin.fl.us
Bud.howard@loxahatcheeriver.org

Restoration Project Website - www.oysterrestoration.com
Reports & Data - www.loxahatcheeriver.org/reports.php

Research Reports » Loxahatchee River District - Microsoft Internet Explorer provided by The Loxahatchee River District

<http://www.loxahatcheeriver.org/reports.php>

Home | Contact Us | Site Map | Employees Only

Loxahatchee River District

Osprey (*Pandion haliaetus*)

American Alligator (*Alligator mississippiensis*)

Preserving Nature by Design

Environmental Protection

General Information

- ABOUT US
- WATCH VIDEO
- ABOUT THE RIVER
- WHAT'S NEW
- CALENDAR

Utility Management

- WASTEWATER FACILITY
- ENGINEERING
- SEPTIC TO SEWER
- DEVELOPMENT

Environmental Education

- THE RIVER CENTER

Studies, Reports & Data

Below is a compilation of much of the water quality and biological research and monitoring programs conducted by the River District's WildPine Ecological Laboratory. If you have questions about these programs, or need more information, please contact the Loxahatchee River District at (561) 747-5700 or wildpine@loxahatcheeriver.org.

- RiverKeeper - Water Quality
- Datasonde - High-Frequency Water Quality Monitoring
- Seagrass - Mapping and Monitoring
- Oyster - Restoration and Monitoring
- Event Sampling - Stormwater Monitoring
- Macroinvertebrates
- River and Watershed Management

Photo Gallery

Latest photos added:
Photography Contest - Winning Photographs.

[more photo galleries »](#)

What's New

River Center's Haunted Hammock Halloween Event
A fun, Peter-Pan themed Halloween event for families! Kids will enjoy arts and crafts