

TAYLOR ENGINEERING, INC.



Twin Rivers Shoreline Stabilization Project

JB Brumfield, P.E.
Jessica Garland
Lauren Theis




February 5, 2026

Presentation Outline

- Location
- Twin River's Park Overview
- Background and Existing Conditions
- Project Goals
- Data Collection
- Design Overview
- Permitting Mechanisms
- Construction Progress and Considerations
- Post-Construction Review

Geographic Location




Geographic Location




Twin River's Park Overview

- 1,400 feet of shoreline
 - 400 feet of seawall/revetment (north)
 - 700 feet of rock revetment/sill with dense mangrove forest (central area)
 - Restored post Hurr. Francis and Jeanne
 - ASBPA 2022 Best Restored Shores Award
 - Pile supported dock that aligns the waterfront
 - **300-foot section in the south experiencing severe ongoing erosion and undermining**
 - One of the largest gopher tortoise concentrations in the State



Existing Site Conditions Prior to Project

- 300 linear feet of severely eroded shoreline
 - Scarps up to 8 feet tall
- 100 feet of shoreline lost over past 25 years
- Mangrove forests align portions of the shoreline
- Dense seagrasses in the nearshore
- Primary cause of erosion
 - Extreme storm events
 - Boat wakes



Project Goals

- Stabilize and protect the eroding shoreline with nature-based features.
- Protect and enhance the critical habitat for local threatened species such as the Gopher Tortoise, West Indian Manatee and the Wood Stork.
- Preserve the park's natural character and safety of public access.



Grant Funding

- 50% project funded by FDEP Resilient Florida Program – Living Shorelines
 - Quarterly progress reports
 - Project metric tracking
 - Project administration
 - Task deliverable form
 - Design and permitting deliverables
 - Construction site observations and reports



DEPARTMENT OF ENVIRONMENTAL PROTECTION
Resilient Florida Program – Implementation Grant
Progress Report Form

Exhibit A

Required for all Resilient Florida Program grant agreements. Complete and send to ResilientFloridaGrants@FloridaDPEP.org no later than twenty (20) calendar days following the completion of the quarterly reporting periods, ending March 31, June 30, September 30, and December 31 (pursuant to Attachment 1, paragraph 10; Status Reports).

DEP Agreement No.:	22SRP05		
Project Title:	Martin County Twin Rivers Park Shoreline Stabilization		
Grantee Name:	Martin County Board of County Commissioners		
Grantee Address:	2401 St. Monterey Rd	Telephone No.:	772-288-5750
Grantee's Grant Manager:	Jessica Garland		
Reporting Period:	10/01/2024 – 12/31/2024		

INSTRUCTIONS: Provide the following information for all tasks and deliverables identified in Attachment 3, Grant Work Plan: (1) task title; (2) description of the work performed during the reporting period; (3) all problems and/or delays encountered, including problem resolutions and/or scheduled updates, where applicable; (4) percentage of the task work that has been completed to date; and (5) any proposed work for the next reporting period.

NOTE: Use as many pages as necessary to cover all tasks in the Grant Work Plan.

The following format should be followed:

Task 1

1. **Task Title:** Design and Permitting
2. **Progress for this reporting period:** All work completed for the final design for the project including drafts of the final plans and specifications.
3. **Identify any delays or problems encountered:**
4. **Percentage of task completed:** 95%
5. **Proposed work for the next reporting period:** Contractor will obtain NPDES permit.

Task 2

1. **Task Title:** Bidding and Contractor Selection
2. **Progress for this reporting period:** None.
3. **Identify any delays or problems encountered:**
4. **Percentage of task completed:** 100%
5. **Proposed work for the next reporting period:** All work is complete for this Task.

Task 3

1. **Task Title:** Construction
2. **Progress for this reporting period:** Pre-construction meeting completed. Notice to proceed issued. Gopher tortoise removal and relocation ongoing. Site mobilization, silt fence installation, and site clearing began.
3. **Identify any delays or problems encountered:**
4. **Percentage of task completed:** 10%
5. **Proposed work for the next reporting period:** Construction will begin following all gopher tortoise relocation and mat installation.

Exhibit A, DEP Agreement # 22SRP05
1 of 4

3/7/2024

Data Collection



Desktop Analyses



Topographic Survey



Bathymetric Survey



Natural Resource Survey

Gopher Tortoise Considerations/Relocation



- Over 70 GT burrows identified
 - 14 within corridor
- Recipient area on-site outside of construction area
- Robust exclusion measures installed
 - Double silt fences
 - Mobi-matts
 - Daily inspections

Mangrove/Sea Grass Considerations



- 0.07 AC Mangroves
- 0.21 AC Shoal Grass
- 0.47 AC Johnsons Sea Grass
- 0.04 AC Paddle Grass

Coastal Conditions Review

- Design Storm
 - 2050 SLR
 - 25-year return period
- Significant Wave Height
 - 3.5 ft
- Peak Wave Period
 - 3.2 sec
- Stone Size
 - Limestone Armor Stone, W_{50} : 918 lbs

Period	Sea Level Rise (ft)	Source
1992 – 2020	0.47	Virginia Key, measured
2020 – 2050	0.74	IPCC MED (Key West), projected
2020 – 2060	1.01	
2020 – 2070	1.33	

Annual Exceedance Probability	Return Period (yrs)	Significant Wave Height (ft)	Peak Wave Period (sec)
10%	10	2.4	2.8
4%	25	3.5	3.2
2%	50	3.9	3.4
1%	100	4.3	3.6




Design Criteria/Approach

- Nature-Based Approach
- Native limestone structures to enhance habitat
 - Two segmented breakwaters
 - Limestone revetment
 - Preserve shoreline access for recreational activities
- Native Plantings
 - White, Red, and Black Mangroves
 - Sea Grapes
 - Buttonwoods





Site Plan



Permitting Mechanisms

- FDEP
 - Sovereignty Submerged Lands Easement
- USACE
 - Nationwide Permit 54 (Living Shorelines)
- SFWMD
 - Individual Environmental Resource Permit




Construction Progress and Overview

- Construction Start: Nov 2024
- Completion: May 2025
- 842 tons of limestone armor
- 213 Sea Grapes
- 141 Button Woods
- Mangrove Planting
 - 40 Red
 - 53 Black
 - 37 White



During Construction Considerations

- Gopher Tortoise Exclusion Controls
 - Double silt fence
 - Mobi-matt corridor
- Updated seagrass survey
- Quarry Site Visit/ Weight Tests
- Pre-planting survey
 - Capture shoreline behavior
 - Identify suitable planting areas



Post-Construction and Planting



1 Year Post-Construction and Planting



THANK YOU
Questions?

